





# DANIELS DRAIN CONSTRUCTION PROJECT

INFORMATIONAL MTG
THURSDAY, AUGUST 26<sup>TH</sup>, 2021 - 6:00 p.m.

MERIDIAN TOWNSHIP MUNICIPAL BUILDING
5151 MARSH RD.
OKEMOS, MI 48864

**TOWN HALL ROOM** 






### **HISTORY**

1923 – Drain first established (8"–18" tile, Pond Excavation)

1973 – Drain construction improvement work on extension Drain

2016 - MERIDIAN TWP. PETITION FOR DRAIN IMPROVEMENTS



#### Survey of Daniels Drain

cated on sections 22 and 23, town 4 north, range 1 west, Meridian of Michigan, Township of Meridian, County of Ingham and State of Micaigan, the centerline thereof being described as follows:


Commencing in the Unruh Drain, at a point 82 ft. S and 328 ft. E of the W ¼ post of section 23, town and range aforesaid, thence over and across the following description: of the gravel road, Oscar J. Becaer and w.fe, Nellie Edith, owners, as follows: Commencions and the commencions of the gravel road elevation, 97.95. The right of way for the commencions of the gravel for the commencions of That part of the W ½ of the NW ¼ of the SW ¼ of said section 23 north plus 00 ft. of said drain, thence S 13° (50) feet on each side o E 600 feet, thence S 4° E 247 feet; hine as above described. thence S 19½° W, 212 feet; to station 10 plus 59 feet in the centerline

Said drain shall be constructed as a closed drain of the following diameters: Station 0 to station 11 plus 50 feet, 18-inch sewer pipe; station 11 plus 50 feet to station 15, 16-inch drain tile; station 15 to station 20, 10-inch drain tile; station 20 to sta-tion 24 plus 50 feet, 8-inch drain tile.

The grade of said drain shall be as follows: Commencing at station 0, grade elevation, 92.20, thence a grade of 0.13% to station 15, grade elevation, 94.15; thence a grade of

tion of said drain shall include fifty (50) feet on each side of the center-

All work of construction shall be according to plans and specifications





2016





### **HISTORY:**





1967



1955



### **HISTORY:**





*1999* 





#### **DRAINAGE ISSUES:**

- Drain has sink holes, collapsed & pipes w/ significant sediment buildup
- Flooding of nearby PCH property, damaged walkways and trees
- Walden Pond outlet issues & undersized crossing of Grand River Ave.









#### **DRAINAGE ISSUES:**

**Estimated Annual Ibs Chloride** 


6,116

3,283

6,746

6,296

Phosphorous and salt pollution from watershed area into Walden Pond










#### **SURVEY OF EXISTING POND (November, 2013):**

- Walden Pond =  $\pm$  2.6 acres
- Filled in 1 to 5 feet throughout









#### **SURVEY OF EXISTING POND (November, 2013):**

• 8,500 CYD material of excavation required to return to 1973 excavated depth





#### DANIELS DRAIN SERVICE AREA – APPORTIONMENT ANALYSIS



MERIDIAN TWP = 82.76%

IC DEPT. OF ROADS = 13.85%

MDOT = 3.39%


**TOTAL PROJECT COST:** +/- \$6,690,000

TOTAL COST OF CONST: \$4,878,235.75 (73% of total project cost)






#### DANIELS DRAIN SERVICE AREA & STORM SEWER SYSTEM








#### **DANIELS DRAIN – PROPOSED CONSTRUCTION SCHEDULE:**







#### **DANIELS DRAIN CONSTRUCTION PROJECT – PROPOSED WORK:**




Repair work on Ivywood, Mistywood & Satinwood





#### **DANIELS DRAIN CONSTRUCTION PROJECT – PROPOSED WORK:**




Complete pipe replacement under Grand River Ave. and north to Unruh Drain





#### **DANIELS DRAIN CONSTRUCTION PROJECT – PROPOSED WORK:**






#### 20,650 CYD of Pond excavation work









#### DANIELS DRAIN SERVICE AREA & STORM SEWER SYSTEM





#### DANIELS DRAIN SERVICE AREA & STORM SEWER SYSTEM





Existing storm sewer pipe replacement, new asphalt roads, re-establish road ditches/swales & install 'rain lawns'








### **QUESTIONS**???

#### **CONTACT INFORMATION DURING CONSTRUCTION**



#### **Daniels Drain Project**

Contact Information:

Ingham County Drain Commissioner Patrick E. Lindemann

517-676-8395

#### **GEI Consultants**

Kyle Smith
Project Engineer
(734) 904-9356
ksmith@geiconsultants.com



#### **GEI Consultants**

Brian J. Cenci, PE Project Manager (517) 449-3478 bcenci@geiconsultants.com

